# Test Report



Report No Client	243/4443363 This Report consists of 10 pages  National Cables Industry P.O.Box 27472 Sharjah U.A.E
Authority & date	Clients order dated 14 November 2002
Items tested	2 samples of Electric Cable
Specification	CEI IEC 60502-1:1997 Including AMD 1
Results	The samples submitted complied with the requirements of the Specification For the tests which were requested
Prepared by	CR Mead IR. Moral Technician
Authorized by	C Yogaratnam C. Yogaratnam Technical Engineer
Issue Date	31 March 2003
Conditions of issue	This Test Report is issued subject to the conditions stated in current issue of <i>PS082</i> 'General conditions relating to acceptance of testing'. The results contained herein apply only to the particular sample/s tested and to the specific tests carried out, as detailed in this Test Report. The issuing of this Test Report does not indicate any measure of Approval, Certification, Supervision, Control or Surveillance by BSI of any product. No extract, abridgement or abstraction from a Test Report may be published or used to advertise a product without the written consent of the General Manager, BSI Product Services, who reserves the absolute right to agree or reject all or any of the details of any items or publicity for which consent may be sought.

#### 1. Introduction

This Report relates to tests conducted on two samples of electric cable submitted by National Cables Industry, Sharjah, U.A.E.

This Report applies only to the particular samples tested and to the specific tests carried out and detailed within the Report. It does not indicate any measure of Approval, Certification, Supervision, Control or Surveillance by BSI of these or any related products.

#### 2. Samples

The client submitted two samples of Electric Cable described as follows;

- 1) 4x300mm<sup>2</sup>
- 2) 4x150mm<sup>2</sup>

#### 3. Testing

The samples submitted were subjected to the tests specified in CEI IEC 60502-1: 1997

#### 4. Results

- Note 1:- The test results were taken from the original test report 243/4351382
- Note 2:- The potential variability in, both the items tested and the method of measurement used, means that for measurements close to a specified limit, the level of confidence in a compliance statement may or may not be reduced.

Further advice on the specific measurements in this report that may be affected can be obtained from the report authoriser shown on the front cover.

The results of the tests carried out are detailed in the following report

#### 5. Conclusion

The samples submitted complied with the requirements of the Specification for the tests which were requested

Report No. 243/4443363

Page 3 of 10 Sample 1 sheet 1

## **TESTING OF CABLE MANUFACTURED TO CEI IEC 60502-1:1997**

4 core Conductor size: 30		
	A	SSESSMENT
Marking		
Embossed on sheath ELECTRIC CABLE 600/1000V BS 5467 4x300 MM2 ( NATIONAL CABLES UAE 2003	CU/XLPE/SWA/PVC	
Marking on 2 line(s) Character size 10 mm. Repeat in	itervals:-466 mm	N/A*
Clauses 5, 7, 12 and 13:- Construction		
Sheath colour Black Filler Textile fibres Extruded bedding Conductor:-Shaped stranded plain annealed Cu Armoured Galvanised steel wire LH Lay	Core lay up RH Size: 2.47 mm	PASS PASS PASS PASS PASS
Clause 15.3:- Voltage Tests:-		
Complete Cable @ 3.5 kV		PASS
Clauses 7.1.3 and 13.3:- Bedding thickness and Ov	versheath thicknes	s
Thickness of oversheath Min 2.57 mm Thickness of extruded bedding Mean 1.36 mm		PASS ,
** No requirement		

*Note :- "The IEC provides	no marking procedure	e to indicate its apr	proval. Therefore no
assessment requi	ed for marking".		

Date samples received	:- 24/01/03	Testing commenced:- 25/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:- 31/03/03	Checked by:- C.Yogaratnam

Report No. 243/4443363 Page 4 of 10 Sample 1 sheet 2

## **TESTING OF CABLE MANUFACTURED TO CEI IEC 60502-1:1997**

4 core				onductor siz	e: 300 sq.mm
					ASSESSMENT
Tests on individual cor	es				
Clauses 5 and 15.2					
Core I.D and sequence Indelibility Class of conductor No. of Wires Conductor resistance	Red P 2 61	Yellow P 2 61	Blue P 2 61	Black P 2 61	PASS PASS PASS PASS
@ 20°C (ohms/km)	0.0593	0.0594	0.0592	0.0592	PASS
Clauses 6.2:- Insulation	n Thickne	ss			
Mean (mm) Min (mm)	2.10 1.66	2.71 2.46	2.67 2.47	2.05 1.81	PASS PASS

Overall assessment:- PASS

Date samples receive	ed:- 24/01/03	Testing commenced:- 28	5/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:- 3	1/03/03	Checked by:- C.Yogaratnam

4 core			Conductor	<b>size:</b> 300 so	mm.p
				ASSESS	SMENT
Clause 18.14:-			, , , , , , , , , , , , , , , , , , ,		D.4.0.0
Flame Test on complete cable					PASS
Clauses 6.1, 13.2,18.3 and 18.5:- Tensile tests on Sheath Compound Tensile strength unaged (N/mm²) Elongation at Break-unaged (%) Tensile strength aged 7 days Air @ % Var Tensile strength aged 7 days Air % Var.Elongation aged 7 days Air % Compatibility Tensile Strength after a Compatibility Elongation @ break aft Compatibility % Var Tensile Strength Compatibility % Var Elongation at break assessment of tensile tests on sheat	in air @ 10 @ 100° C g 100° C ageing er ageing l eak	1 3 1 00° C -: 3 4 1	9.9 325 3		PASS
Tensile tests on Cores Compound	XLPE				
Tensile strength unaged (N/mm²) Elongation at Break-unaged (%) % Var Tensile strength, aged 7 days	Red 26.3 636 @ 135° 0	Yellow 27.1 632 2 air 7	Blue 28.0 645	Black 29.6 649	
% Var.Elongation at break, aged 7 da		•	7	-1	
% Var Tensile strength, aged with Cl		-	_		
% Var.Elongation at break, aged with					
Compatibility Tensile Strength after a	-13 ageing 26.5	-14 28.6	-17 26.2	-10 27.3	
Compatibility Elongation @ break aft		613	585	595	
Compatibility % Var Tensile Strength Compatibility % Var Elongation at bre	1	5	-7	-8	
. , ,	-3	-3	-9	-8	
Assessment of tensile tests on cores					PASS
			OII		DACC

Date samples receive	ed:- 24/01/03	Testing commenced:-	25/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:-	31/03/03	Checked by:- C.Yogaratnam

N/A = Not Applicable

N/R = Not Requested

N/T = Not Tested

Overall assessment :-

**PASS** 

Report No. 243/4443363

Page 6 of 10 Sample 1 sheet 4

### **TESTING OF CABLE MANUFACTURED TO CEI IEC 60502-1:1997**

4 core		C	Conductor size: 300 sq.mm		
				ASSESS	SMENT
Tests on Sheath or complete cab					
Clauses 18.6, 18.7, 18.8 and 18.9:					
Compound Cold elongation @ -15° C			ST2		PASS
Cold Impact @ -15° C Loss of mass mg/cm²			0.7 28		PASS PASS PASS
Hot pressure (%) Heat shock test			PASS		PASS
Tests on individual cores					
Clauses 6.1, 16.9, 17.2, 18.13 and	18.16:-				
Compound CORE COLOURS Hot set test Max Elongation % Hot set test Permanent Elongation Water absorption (Gravimetric) mg/d	XLPE Red 78 5 cm <sup>2</sup>	Yellow 68 5	Blue 63 5	Black 70 5	PASS PASS
, , ,	0.03	0.02	0.05	0.04	PASS
Volume resistivity @ 90° C ohms.cm	า 4.3x10 <sup>16</sup>	1.9x10 <sup>16</sup>	2.7x10 <sup>16</sup>	4.9x10 <sup>16</sup>	PASS
Insulation resistance constant @ 90	° C Mohms				
Voltage test for 4 hours % Shrinkage of cores after test 1hr (	11.76 PASS	14.85 PASS	76.71 PASS	25.22 PASS	PASS PASS
70 Stillinkage of cores after test till (	2.5	2.5	2.5	2.5	PASS
		Ov	erall asses	ssment:-	PASS

# The sample complied with the requirements of the standard

Date samples receive	d:- 24/01/03	Testing commenced:- 2	25/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:-	31/03/03	Checked by:- C.Yogaratnam

4 core	Conductor size: 150 sq.mm
	ASSESSMENT
Marking	
Embossed on sheath ELECTRIC CABLE 600/1000V BS 5467 4x150 NATIONAL CABLES UAE 2002	MM2 CU/XLPE/SWA/PVC
Marking on 2 line(s) Character size 6 mm. Rep	eat intervals:-495 mm N/A*
Clauses 5, 7, 12 and 13:- Construction	
Sheath colour Black Filler Textile fibres Extruded bedding Conductor:-Shaped stranded plain annealed Cu Armoured Galvanised steel wire LH Lay	
Clause 15.3:- Voltage Tests:-	
Complete Cable @ 3.5 kV	PASS
Clauses 7.1.3 and 13.3:- Bedding thickness	and Oversheath thickness
Thickness of oversheath Min 2.47 mm Thickness of extruded bedding Mean 1.38 mm	m PASS
** No requirement	

<sup>\*\*</sup> No requirement

Date samples received:-	24/01/03	Testing commenced:- 25/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:- 31/03/03	Checked by:- C.Yogaratnam

<sup>\*</sup>Note :- "The IEC provides no marking procedure to indicate its approval. Therefore no assessment required for marking".

4 core Conductor siz					e: 150 sq.mm	
					ASSESSMENT	
Tests on individual core	es			W = A = = = 9		
Clauses 5 and 15.2						
Core I.D and sequence Indelibility Class of conductor No. of Wires Conductor resistance	Red P 2 37	Yellow P 2 37	Blue P 2 37	Black P 2 37	PASS PASS PASS PASS	
@ 20°C (ohms/km)						
Mean (mm) Min (mm)	1.50 1.29	1.64 1.45	1.55 1.39	1.69 1.39	PASS PASS	

Overall assessment: - PASS

\*Note:- The resistance value of the Yellow core falls within the range of Uncertainty of measurement. Uncertainty of the measurement is ± 0.32% Of the measured value.

Date samples received:- 24/01/03		Testing commenced:	- 25/02/03	Tested by:-	C.R.Mead
Date job raised:-	19/07/02	Testing completed:-	31/03/03	Checked by:	- C.Yogaratnam

4 core			Conductor size: 150 sq.mm		
				ASSESS	SMENT
Clause 18.14:- Flame Test on complete cable					PASS
Clauses 6.1, 13.2, 18.3 and 18.5:- Tensile tests on Sheath Compound Tensile strength unaged (N/mm²) Elongation at Break-unaged (%) Tensile strength aged 7 days Air @ 1 % Var Tensile strength aged 7 days Air % Var.Elongation @ break aged 7 days Air @ Compatibility Tensile Strength after a Compatibility Elongation @ break afte Compatibility % Var Tensile Strength Compatibility % Var Elongation at break Assessment of tensile tests on sheate Tensile tests on Cores	n air @ 10 @ 100° C 100° C geing er ageing eak		5 2 3		PASS
Compound  Tensile strength unaged (N/mm²) Elongation at Break-unaged (%) % Var Tensile strength, aged 7 days	XLPE Red 26.7 621 @ 135° 0	Yellow 29.2 655 Cair	Blue 28.8 671	Black 26.9 627	
% Var.Elongation at break, aged 7 da	1 iys @ 135	1 5° C air	1	6	
% Var Tensile strength, aged with CU	-6 I conducto 5	-7 or 7 days @ -5	-4 135° C air -5	-4 -2	
% Var. Elongation at break, aged with	CU condi				
Compatibility Tensile Strength after a	27.0	27.4	25.5	28.2	
Compatibility Elongation @ break after Compatibility % Var Tensile Strength	er ageing 583 1	593 -6	628 -11	622 5	
Compatibility % Var Elongation at bre	•	-9	-6	-1	
Assessment of tensile tests on cores					PASS
					DACC

Date samples received:- 24/01/03	Testing commenced:- 25/02/03	Tested by:- C.R.Mead	
Date job raised:- 19/07/02	Testing completed:- 31/03/03	Checked by:- C.Yogaratnam	

N/A = Not Applicable

N/R = Not Requested

N/T = Not Tested

Overall assessment :-

**PASS** 

4 core		C	Conductor size: 150 sq.mm		
				ASSESS	SMENT
Tests on Sheath or complete cab	le	. 또 본 도 도 문 해 위 및 로 로 등 등 차 1			
Clauses 11.1:-					
Compound Cold elongation @ -15° C Cold Impact @ -15° C			ST2		PASS PASS
Loss of mass mg/cm² Hot pressure (%) Heat shock test			0.61 30 PASS		PASS PASS PASS
Tests on individual cores					
Clauses 6.1,16.9, 17.2, 18.13 and	18.16:-				
Compound CORE COLOURS Hot set test Max Elongation % Hot set test Permanent Elongation Water absorption (Gravimetric) mg/c	XLPE Red 63 5 cm <sup>2</sup> 0.01	Yellow 60 0	Blue 65 3	Black 70 5	PASS PASS PASS
Volume resistivity @ 90° C ohms.cm		0.06	0.03	0.05	PASS
Insulation resistance constant @ 90	2.7x10 <sup>16</sup>	1.9x10 <sup>16</sup> s.km	1.7x10 <sup>16</sup>	2.7x10 <sup>16</sup>	PASS
Voltage test for 4 hours % Shrinkage of cores after test 1hr (	4.46 PASS	4.57 PASS	5.09 PASS	11.6 PASS	PASS PASS
The state of the s	2.5	1.5	2.0	2.0	PASS
		Ov	erall asses	ssment:-	PASS

# The sample complied with the requirements of the standard

Date samples receive	ed:- 24/01/03	Testing commenced:- 25/02/03	Tested by:- C.R.Mead
Date job raised:-	19/07/02	Testing completed:- 31/03/03	Checked by:- C.Yogaratnam